



**LEGEND:**

CONCRETE PAVEMENT, SIDEWALK AND CURB RAMP REPAIR

**NOTES:**

1. THE CONTRACTOR SHALL INSTALL BLOCK SOD OVER 4" OF TOPSOIL IN ALL DISTURBED AREAS AT A COST SUBSIDIARY TO THE PROJECT. SOD SHALL MATCH THE TYPE OF GRASS TO BE REPLACED.
2. CONTRACTOR SHALL AVOID DAMAGE TO ALL EXISTING STRUCTURES OR FLATWORK TO REMAIN. ANY DAMAGE SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
3. PAVEMENT TO BE REMOVED IN SUCH MANNER THAT THE ENTIRE PANEL OR HALF A PANEL OF CONCRETE IS REPLACED TO AVOID LEAVING NARROW STRIPS OF EXISTING PAVEMENT. CONTRACTOR SHALL MATCH EXISTING JOINTS WHERE APPLICABLE.
4. CONCRETE PAVEMENT REMOVAL AND REPLACEMENT SHALL INCLUDE ANY MONOLITHIC CURB PAID FOR SUBSIDIARY TO THE CONCRETE PAVEMENT BID ITEM.
5. CONCRETE PAVEMENT, DRIVEWAY AND SIDEWALK LIMITS SHOWN SHALL MATCH GRADES OF EXISTING PAVEMENT, DRIVEWAY AND/OR SIDEWALK, WITH ANY NECESSARY JOINTS PER TOWN DETAILS.

FILE NAME: A:\37000\37638\124\PM\CADD\Sheets\C-PLAN-PAV-01-37638.dwg DATE: August 15, 2024, TIME: 2:25 PM, USER: ah5462

NO.	DATE	DESCRIPTION

DESIGNED BY:  
BSV  
DRAWN BY:  
KJG  
CHECKED BY:

2601 MEACHAM BLVD., SUITE 600  
FORT WORTH, TEXAS 76137  
TEL. (817) 847-1422

NAME: KEVIN J. GRONWALDT  
DATE: 8/15/2024  
TBPELS ENG. FIRM #F-312

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY:  
NAME: KEVIN J. GRONWALDT  
DATE: 8/15/2024  
THE RECORD COPY OF THIS DRAWING IS ON FILE AT THE OFFICES OF:  
HALFF ASSOCIATES, INC.  
2001 MEACHAM BLVD STE 600  
FORT WORTH, TEXAS 76137  
TBPELS ENGINEERING FIRM #F-312  
FIRM OR BUSINESS NO.

City-close, lakeside living!

TOWN OF HICKORY CREEK  
FY2024 PAVEMENT REPAIRS AND PHASE 4 SIDEWALK EXTENSION  
POINT VISTA ROAD AND NORTH FIELD CIRCLE  
PAVEMENT AND CURB REPAIR

PROJECT NO.: 37638.124  
ISSUED: 8/15/2024  
SCALE: 1" = 30'  
**4**  
PAGE NUMBER 4 OF 42